KOLAR DIVISION.

Notice, dated 8th January 1917.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 11 A.M. on 26th January 1917, for the restoration of Ildone Tank, Register No. 147 of Srinivaspur Taluk, Kolar District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1917.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M., on all office working days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 (rupees two hundred and fifty only) in cash or Government promissory notes, as earnest money, and be superscribed "Tender for the restoration of Ildone Tank, Register No. 147, Srinivaspur, Taluk, Kolar District," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Kolar Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring the Ildone Tank, Register No. 147 of Srinivaspur Taluk.

Items of work	Per	Rate.
Bund to be raised to R. L. 55·00.		
1. Earthwork, excavation including forming, watering and tamping, etc., complete.	C. yd.	7,850
2. Turfing	S. yd.	7,483
3. Resetting the old stone work	C. yd.	150
4. New stone work	"	588·42
5. Providing grade stones with bed slab including painting	Each.	40
6. Do do index stone	"	40
7. Do do Registered No. stone	"	1
8. Do do date stone	"	1
9. Refixing the existing B. M. stones	"	2
10. Providing gauge stones	"	1
11. Cutting trenches and clearing jungle	Lump sum.	Rupees.
Sluice.		
Sluice No. 1.		
1. Examining the sluice and repairing the front cistern	Lump sum.	Rupees.
2. Providing plug and rod with locking arrangement	"	"
Sluice No. 2.		
(1) Providing plug and rod with gearing arrangement	Lump sum.	Rupees.
Waste weir (Left) 156' long.		
1. Earthwork excavation	C. yd.	567
2. Concrete in surki mortar	C. ft.	473
3. Burnt brick in surki mortar	C. yd.	1,542
4. Burnt stone slabs dressed	C. ft.	508
5. Plastering with surki mortar	Sq.	9·94
6. Providing joggles	Each.	40
7. Rough stone work, new	C. yd.	421
8. Clearing draft front and rear	Lump sum.	Rupees.
Waste weir right (existing).		
1. Clearing site in front of toe wall	Lump sum.	Rupees.
2. Dismantling masonry	C. ft.	113
3. Burnt brick in surki mortar	"	676
4. Burnt stone slabs, dressed	"	171
5. Plastering with surki mortar	Sq.	4·75
6. Providing joggles	Each.	17
7. Jelly wedging to apron	C. yd.	20
8. New stone work	"	8
9. Earthwork to wings	Lump sum.	Rupees.

V. AIYASWAMI IYER,
Executive Engineer.

4 c